

## FUTURE FISHERIES IMPROVEMENT PROGRAM GRANT APPLICATION

Please fill in the highlighted areas  
all sections (IA, IB, IC, etc.) must be addressed or the application will be considered invalid

### I. APPLICANT INFORMATION

- A. Applicant Name: Big Blackfoot Chapter of Trout Unlimited
- B. Mailing Address: PO Box 1
- C. City: Ovando State: MT Zip: 59854  
Telephone: 406-240-4824 E-mail: ryen@montanatu.org
- D. Contact Person: Ryen Neudecker  
Address if different from Applicant: See above  
City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_  
Telephone: \_\_\_\_\_ E-mail: \_\_\_\_\_
- E. Landowner and/or Lessee Name (if other than Applicant): United States Forest Service-George Liknes, Fish Biologist  
Mailing Address: 1569 US HWY 200  
City: Lincoln State: MT Zip: 59639  
Telephone: 406.362.7003 E-mail: georgealiknes@fs.fed.us

### II. PROJECT INFORMATION\*

- A. Project Name: North Fork Keep Cool Fish Passage  
River, stream, or lake: North Fork Keep Cool  
Location: Township: 15N Range: 8W Section: 28 SE1/4  
Latitude: 112 42' 39" Longitude: 46 58' 17" N *within project (decimal degrees)*  
County: Lewis & Clark
- B. Purpose of Project:  
The purpose of this project is to replace an undersized culvert near stream mile 10.1 on North Fork Keep Cool Creek that prevents fish passage for native trout at nearly all flows and creates impairments to the channel.
- C. Brief Project Description: \_\_\_\_\_

NF Keep Cool Creek fish passage

North Fork Keep Cool Creek is a third-order tributary to Keep Cool Creek and supports fluvial, genetically pure westslope cutthroat trout. Keep Cool is a tributary to the upper Blackfoot River and enters the river just west of Lincoln, MT. This project has been identified as a priority under the **Collaborative Forest Landscape Restoration Program**—a program identified in 2009 by the Secretary of Agriculture to encourage the collaborative, science-based ecosystem restoration of priority forest landscapes. This project will address the existing stream crossing near stream-mile 10.1 on the United States Forest Service lands that is undersized, is a fish passage barrier at most flows and creates impairments to the channel. The existing 87” pipe arch culvert is proposed to be replaced with a bottomless steel plate pipe arch structure that will allow uninhibited aquatic organism passage and replicate the stream bed up and down stream of the crossing.

The existing undersized culvert on North Fork Keep Cool Creek causing channel impairment, lack of connectivity, and depression of migratory life histories is proposed to be replaced with a bottomless arch structure following Stream Simulation methods and principles that will result in a stable stream crossing that will correct the current road drainage problems, eliminate delivery of excessive sediment, provide for fish passage (1.3 mile additional connectivity upstream of the crossing) and restore the natural channel morphology to the site. A basic topographic and hydraulic field survey was conducted to locate key physical features within the area of the existing culvert. A long profile, stream cross-sections, bankfull widths, and general geomorphologic parameters were collected. The new structure dimensions were sized based on stream characteristics collected from the reference reach and hydraulic analysis. The hydraulic capacity of the structure was analyzed to ensure that it satisfies a 100-year flood event. Reference reach data collected indicated that bankfull width is close to 12 ft., 5 inches. To meet Stream Simulation guidelines, our new structure width will be 17’ to accommodate bankfull and an appropriate floodplain. Grade control step pools will also be incorporated as the channel grade is close to 5.2%. Please refer to attached map, photos and design.

D. Length of stream or size of lake that will be treated:

The existing undersized culvert near stream mile 10.1 will be replaced to restore connectivity to 1.3 miles of NF Keep Cool Creek with waters downstream.

E. Project Budget:

**Grant Request (Dollars): \$ 22,400.00**

Contribution by Applicant (Dollars): \$ 4,000 In-kind \$ 6,735  
(salaries of government employees are not considered as matching contributions)

Contribution from other Sources (Dollars): \$ 139,512.50 In-kind \$  
(attach verification - See page 2 budget template)

**Total Project Cost: \$ 172,647.50**

F. Attach itemized (line item) budget – see template

Attach **specific project plans, detailed sketches, plan views, photographs, maps, evidence of landowner consent, evidence of public support and fish biologist support, and/or other**

G. **information necessary to evaluate the merits of the project. If project involves water leasing or water salvage complete a *supplemental questionnaire***  
(fwp.mt.gov/habitat/futurefisheries/supplement2.doc).

H. **Attach land management & maintenance plans that will ensure protection of the reclaimed area.**

### III. PROJECT BENEFITS\*

A. What species of fish will benefit from this project?:

Pure populations of westslope cutthroat trout.

B. How will the project protect or enhance wild fish habitat?:

Upgrading this undersized stream crossing will restore fish passage and reconnect ~ 1.3 miles of instream habitat upstream of the crossing. The immediate reach of North Fork Keep Cool Creek where the culvert is located may go dry during late summer months in some years, but the stream reaches up and downstream remain perennial. Allowing trout to move freely through this reach before flows go subsurface is important to maintain population connectivity and increase the long term viability and persistence of the population.

C. Will the project improve fish populations and/or fishing? To what extent?:

The project will improve recruitment of westslope cutthroat trout within the drainage and downstream.

D. Will the project increase public fishing opportunity for wild fish and, if so, how?:

Yes, by increasing wild trout habitat in the Blackfoot River drainage. The public also has legal streamside access via adjacent USFS lands.

E. The project agreement includes a 20-year maintenance commitment. Please discuss your ability to meet this commitment.

The USFS has committed to maintaining the bottomless arch steel plate pipe arch for its life expectancy. The proposed structure will be essentially maintenance-free structures and the life expectancy is estimated to be between 75 and 100 years.

F. What was the cause of habitat degradation in the area of this project and how will the project correct the cause?:

The cause of degradation is the undersized culvert installed at an elevation too high to allow fish passage. Upgrading the stream crossing will correct the impairments.

G. What public benefits will be realized from this project?:

This project involves the continuation of the Blackfoot River Restoration program and the restoration of a westslope cutthroat stream. Public benefits include: 1) recruitment of recreational fisheries to the Blackfoot River, 2) improved water quality (sediment reductions) on-site and downstream, and 3) contribute to the recovery of a species of special concern.

H. Will the project interfere with water or property rights of adjacent landowners? (explain):

No impact to any water rights or property rights of adjacent landowners will occur.

I. Will the project result in the development of commercial recreational use on the site?: (explain):

No commercial recreational use is known to occur on this project site.

J. Is this project associated with the reclamation of past mining activity?

No

**Each approved project applicant must enter into a written agreement with Montana Fish, Wildlife & Parks specifying terms and duration of the project. The applicant must obtain all applicable permits prior to project construction. A competitive bid process must be followed when using State funds.**

**IV. AUTHORIZING STATEMENT**

I (we) hereby declare that the information and all statements to this application are true, complete, and accurate to the best of my (our) knowledge and that the project or activity complies with rules of the Future Fisheries Improvement Program.

Applicant Signature:



Date:

11-28-2017

Sponsor (if applicable):

**\*Highlighted boxes will automatically expand.**

**Mail To:** Montana Fish, Wildlife & Parks  
Fisheries Division  
PO Box 200701  
Helena, MT 59620-0701

**E-mail To:** Michelle McGree  
[mmcgree@mt.gov](mailto:mmcgree@mt.gov)  
(electronic submissions MUST be signed)

Incomplete or late applications will be rejected and returned to applicant.  
Applications may be rejected if this form is modified.

**\*\*\*Applications must be signed and *received* by the Future Fisheries Program Officer in Helena before December 1 and June 1 of each year to be considered for the subsequent funding period.\*\*\***

NF Keep Cool Creek fish passage



Photos 1-2: Existing stream crossing on NF Keep Cool Creek near stream-mile 10.1.

NF Keep Cool Creek fish passage


WORK ITEMS (ITEMIZE BY CATEGORY)	NUMBER OF UNITS	UNIT DESCRIPTION*	COST/UNIT	TOTAL COST	CONTRIBUTIONS			
					FISHERIES REQUEST	IN-KIND SERVICES	IN-KIND CASH	TOTAL
<b>Personnel</b>								
Survey	24	hours	\$100.00	\$ 2,400.00			\$ 2,400.00	\$ 2,400.00
Design	75	hours	\$100.00	\$ 7,500.00			\$ 7,500.00	\$ 7,500.00
Engineering	60	hours	\$90.00	\$ 5,400.00			\$ 5,400.00	\$ 5,400.00
Permitting	20	hours	\$45.00	\$ 900.00		\$900		\$ 900.00
Oversight	125	hours	\$86.50	\$ 10,812.50		4,000.00	6,812.50	\$ 10,812.50
Labor	80	hours	\$45.00	\$ 3,600.00			3,600.00	\$ 3,600.00
				\$ 30,612.50				\$ 30,612.50
<b>Travel</b>								
Mileage	2000	miles	\$0.58	\$ 1,160.00		1,160.00		\$ 1,160.00
Per diem	15	days	\$45.00	\$ 675.00		675.00		\$ 675.00
				\$ 1,835.00				\$ 1,835.00
<b>Construction Materials****</b>								
Placed riprap, class 4	138	cubic yards	\$100.00	\$ 13,800.00			\$13,800	\$ 13,800.00
Seeding, revegetation	LS	each	\$5,000.00	\$ 5,000.00	1,000.00		\$4,000	\$ 5,000.00
Dewatering, Soil erosion, pollution control	LS	each	\$12,000.00	\$ 12,000.00			\$12,000	\$ 12,000.00
Grade Control Structures	5	each	\$4,000.00	\$ 20,000.00	2,000.00		18,000.00	\$ 20,000.00
Precast concrete member, footings	LS	each	\$30,000.00	\$ 30,000.00	3,400.00		26,600.00	\$ 30,000.00
Structural Plate Arch	LS	each	\$28,000.00	\$ 28,000.00	10,000.00		18,000.00	\$ 28,000.00
				\$ 108,800.00				\$ 108,800.00
<b>Equipment</b>								
Hydraulic Excavator	150	hours	\$140.00	\$ 21,000.00	4,000.00		17,000.00	\$ 21,000.00
Dump Truck	60	hours	\$90.00	\$ 5,400.00	2,000.00		3,400.00	\$ 5,400.00
				\$ 26,400.00				\$ 26,400.00
<b>Mobilization</b>								
Mob/demob	1	lump sum	\$5,000.00	\$ 5,000.00	-		5,000.00	\$ 5,000.00
			<b>TOTALS</b>	\$ 172,647.50	\$ 22,400.00	\$ 6,735.00	\$ 143,512.50	\$ 172,647.50

**MATCHING CONTRIBUTIONS**


CONTRIBUTOR	IN-KIND SERVICE	IN-KIND CASH	TOTAL	Secured? (Y/N)
US Forest Service	-	\$ 139,512.50	\$ 139,512.50	YES

NF Keep Cool Creek fish passage

<b>Big Blackfoot Chapter of Trout Unlimited</b>	\$ 6,735.00	\$ 4,000.00	\$ 10,735.00	YES
---	-------------	-------------	--------------	-----



# KEEP COOL CREEK AQUATIC ORGANISM PASSAGE CULVERT REPLACEMENT LINCOLN, MONTANA



PREPARED FOR:  
BIG BLACKFOOT CHAPTER  
OF TROUT UNLIMITED  
P.O. BOX 1  
OVANDO, MONTANA



PREPARED BY:



**SHEET INDEX**

SHEET NO.	TITLE
G1	COVER SHEET
G2*	SITE MAP, GENERAL NOTES, AND CONTROL POINTS
PP1	ROAD PLAN AND PROFILE
PP2	STREAM PLAN AND PROFILE
D1	FOUNDATION DETAILS
D2	STREAM SIMULATION DETAILS
D3	CONCEPTUAL STREAM DIVERSION DETAILS
XS1	ROAD CROSS SECTIONS

NOT TO SCALE

\* NOT INCLUDED IN THIS PRELIMINARY DESIGN SUBMITTAL

RECOMMENDED:

DISTRICT RANGER  
LINCOLN RANGER DISTRICT

Date

REVIEWED:

FOREST ENGINEER  
HELENA NATIONAL FOREST

Date

APPROVED:

FOREST SUPERVISOR  
HELENA NATIONAL FOREST

Date

APPROVED:

Jeffrey K. Olsson, P.E. 18996  
PROJECT MANAGER  
DOWL

Date



**PRELIMINARY  
NOT FOR CONSTRUCTION**

PROJECT 4626.11478.01  
DATE NOVEMBER 2017

SHEET

G1

NF Keep Cool Creek fish passage



REV	DATE	DESCRIPTION	BY



KEEP COOL CREEK CULVERT REPLACEMENT  
FRS 1800

ROAD PLAN AND PROFILE

PROJECT 4637.12022.01  
DATE NOVEMBER 2017







© DOWL 2017  
SHEET

**PRELIMINARY**

PP1

C:\Civil 3D Projects\2014\37\12022-01\Civil\MCI4-CH-IR-12022-01.dwg PLOT DATE 2017-11-17 11:35 SAVED DATE 2017-11-17 11:35 USER: jsimkins

C:\Civil\_3D\Projects\2014\37\12022-01\Civil\MC14-CH-IR-12022-01.dwg PLOT DATE 2017-11-17 11:38 SAVED DATE 2017-11-17 11:35 USER: jsimkins



\* DIMENSIONS OTHER THAN SHOWN ARE ACCEPTABLE IF STANDARD MANUFACTURER'S END TREATMENTS ARE USED. SUBMIT FOR APPROVAL

**PRELIMINARY**


REV	DATE	DESCRIPTION	BY



KEEP COOL CREEK CULVERT REPLACEMENT  
FRS 1800  
STREAM PLAN AND PROFILE


PROJECT 4637.12022.01  
DATE NOVEMBER 2017  
© DOWL 2017  
SHEET  
PP2

REV	DATE	DESCRIPTION	BY



**1**  
D1  
**DETAIL**  
**FOOTING DETAIL**  
NOT TO SCALE


- NOTES:**
- 1 1/2" CLEAR COVER UNLESS OTHERWISE NOTED.
  - PLACE GEOCELL ON UNDISTURBED SOIL. FILL GEOCELL WITH COARSE GRANULAR BACKFILL (SEE SPECIFICATION SECTION 02222).
  - PLACE GEOTEXTILE UNDER GEOCELL AND WRAP OVER TOP AFTER GEOCELL IS BACKFILLED. OVERLAP JOINTS A MINIMUM OF 12 INCHES.



\*ALTERNATIVE LOCATIONS (ON EACH SIDE OF STEM WALL) FOR POST-INSTALLED ANCHORS/PLATE ALTERNATIVE

- NOTE:**
- CONSIDER STAGED CONSTRUCTION WHEN DETERMINING PRECAST SEGMENT LENGTHS.


**4**  
D2  
**DETAIL**  
**TYPICAL PRECAST SEGMENT**  
NOT TO SCALE




**2**  
D1  
**DETAIL**  
**GROUT CHANNEL**  
SCALE IN FEET

\* L 2 1/2 x 2 1/2 x 3/8 IS THE MINIMUM SIZE ANGLE ALLOWED. A LARGER ANGLE, IN EITHER LEG DIMENSION, THICKNESS, OR BOTH MAY BE USED AT CONTRACTOR'S DISCRETION. UNEQUAL LEG ANGLES ARE ACCEPTABLE. ANGLE AND DOWEL ASSEMBLY SHALL BE CAST-IN-PLACE.


\*\* HEIGHT OF INSIDE FIN MAY VARY FROM 2"-4". IF A HEIGHT > 2" IS USED, IT MUST BE VERIFIED THE PLATE ARCH WILL CLEAR THE FIN WHEN SET IN ITS PROPER LOCATION.



**3**  
D1  
**DETAIL**  
**STEM WALL INSTALLATION**  
SCALE IN FEET




**PLAN**




**ELEVATION**

**BOLTED ALTERNATIVE**

**5**  
D2  
**DETAIL**  
**MECHANICAL SPLICE**  
NOT TO SCALE




**PLAN**




**ELEVATION**

**WELDED ALTERNATIVE**




**ELEVATION**

**POST-INSTALLED ANCHORS ALTERNATIVE**




PLAN




ELEVATION


1  
D2  
**DETAIL**  
TYPICAL STEP LOG POOL  
NOT TO SCALE




PLAN  
ROCK WEIR LAYOUT




PLAN



2  
D2  
**DETAIL**  
TYPICAL LOG STEP POOL  
NOT TO SCALE



3  
D2  
**DETAIL**  
ROCK WEIR  
NOT TO SCALE



ELEVATION

4  
D2  
**DETAIL**  
ROCK WEIR  
NOT TO SCALE

**PRELIMINARY**

REV	DATE	DESCRIPTION	BY




KEEP COOL CREEK CULVERT REPLACEMENT  
FRS 1800  
**STREAM SIMULATION  
DETAILS**

PROJECT 4637.12022.01  
DATE NOVEMBER 2017

© DOWL 2017  
SHEET

D2


C:\Civil 3D Projects\2014\37\12022-01\Civil\MC14-CH-IR-12022-01.dwg PLOT DATE 2017-11-17 11:39 SAVED DATE 2017-11-17 11:35 USER: jsimkins




1  
D1  
**DETAIL**  
CONCEPTUAL DEWATERING & SEDIMENT CONTROL PLAN  
NOT TO SCALE

**NOTES:**

- CONTRACTOR SHALL PREPARE FOR REVIEW AND APPROVAL A SOIL EROSION AND POLLUTION CONTROL PLAN TO INCLUDE STREAM DEWATERING/DIVERSION METHODS IN ACCORDANCE WITH SPECIFICATIONS AND THESE PLANS. DETAILS SHOWN ON THIS SHEET ARE CONCEPTUAL AND PROVIDE GUIDANCE OF METHODS AND MEANS THAT WOULD BE ACCEPTABLE.
- WHEN CONSTRUCTING STREAM DIVERSION CONTRACTOR SHALL CAREFULLY REMOVE SOD AND TOPSOIL THAT LIES ALONG THE DIVERSION PATH AND STOCKPILE IN A LOCATION APPROVED BY THE ENGINEER. AFTER REMOVING THE DIVERSION STRUCTURE AND BACKFILLING THE TRENCH, CONTRACTOR SHALL CAREFULLY REPLACE THIS STOCKPILED MATERIAL. PRIORITY AREAS FOR REPLACEMENT OF VEGETATION ARE STREAMBANKS AND FLOODPLAINS.
- CONSTRUCT TEMPORARY SEDIMENT EROSION CONTROLS AROUND TEMPORARY STOCKPILES AND STAGING AREAS. TEMPORARY CONTROLS MAY INCLUDE SILT FENCES, STRAW WADDLES OR BALES, EROSION CONTROL MATTING OR MULCH.



2  
D2  
**DETAIL**  
SANDBAG BYPASS DAM  
NOT TO SCALE



3  
D2  
**DETAIL**  
GEOTEXTILE-WRAPPED STRAW BALE DAM  
NOT TO SCALE

REV	DATE	DESCRIPTION	BY



KEEP COOL CREEK CULVERT REPLACEMENT  
FRS 1800  
**CONCEPTUAL STREAM DIVERSION  
DETAILS**





PROJECT 4637.12022.01  
DATE NOVEMBER 2017

© DOWL 2017  
SHEET

**PRELIMINARY**

D3

C:\Civil\_3D\Projects\2014\37\12022-01\Civil\MCI4-CH-IR-12022-01.dwg PLOT DATE 2017-11-17 11:39 SAVED DATE 2017-11-17 11:35 USER: jsimkins



REV	DATE	DESCRIPTION	BY



KEEP COOL CREEK CULVERT REPLACEMENT  
FRS 1800  
ROAD CROSS SECTIONS

PROJECT 4637.12022.01  
DATE NOVEMBER 2017

© DOWL 2017  
SHEET

XS1

**PRELIMINARY**

C:\Civil\_3D\Projects\2014\37\12022-01\Civil\MCI4-CH-IR-12022-01.dwg PLOT DATE 2017-11-17 11:40 SAVED DATE 2017-11-17 11:35 USER: jsimkins